BRUHAT BANGALORE MAHANAGARA PALIKE

(22)

BBMP/2014-15/OW/WORK_INDENT16515

APPROVED SCHEDULE - B

No.EE(TP)TP/BBMP/E-PMT/08/2014-15, Date: 30.12.2014

Name of work: Construcion of Division Office building in ward no. 8, Kodigehalli sub division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K.V. Subbareddy	
				In Figures	In Words
1	2.02	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unservicea ble material and stacking the serviceable material with all lifts complete as per specifications. - RCC grade M20 and above	cum	983.42	Rupees Nine Hundred Eighty Three and Forty Two Paise Only
2	9.88	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unservicea ble material and stacking the serviceable material with all lifts complete as per specifications. - Dismantling brick work in cement morta	cum	233.62	Rupees Two Hundred Thirty Three and Sixty Two Paise Only
3	43.48	KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications	cum	6358.88	Rupees Six Thousand Three Hundred Fifty Eight and Eighty Eight Paise Only
4	6.93	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 24 kg with 12mm and downsize graded granie metal coarse aggregaes @ 0.051 cum and fine aggregates @ 0.034 cum, with super plastisiser @ 0.225 lts, machine mixed, well compacted for plain chajja of 7.5 cm average thickness, upto ground floor level, including cost of all materials, laobur, HOM of machinery, finishing curing complete as per specifications	cum	482.81	Rupees Four Hundred Eighty Two and Eighty One Paise Only
5	4.34	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications	Tonne	80818.72	Rupees Eighty Thousand Eight Hundred Eighteen and Seventy Two Paise Only

Exe.Engr.
Btp Dn.

6	414.02	KSRB 4-6.2 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications.	sqm	589.61	Rupees Five Hundred Eighty Nine and Sixty One Paise Only
7	21.62	KSRB 6-2.3 Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 50 (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications	cum	6609.18	Rupees Six Thousand Six Hundred Nine and Eighteen Paise Only

K.V. Subba Reddy
Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92